

# 14' Span x 9' Rise ADSPAN® 3-Sided Culvert




Advance Concrete Products Company

(800) 824-8351 (248) 887-4173 Fax: (248) 887-2755

All Concrete Shall Have A Minimum 28 Day Compressive Strength Of 5000 PSI.

Reinforcing Steel Shall Comply With ASTM A615 Grade 60 Rebar.  
Epoxy Coated Rebar or Corrosion Inhibiting Admixture Available.  
All Reinforcement Will Be Wire-Tied.

Design Will Be Based On Your Required Loading Conditions:  
AASHTO HS 20 Wheel Loading, HS 25, HL-93, Alternate Military,  
Toll Road, Aircraft Loading or Other.  
Various Angles Available For Wingwalls.  
Culvert May Be Skewed And Openings Cast-In During Production.



## ADSPAN® ADSPAN® LS

Spans Up To 36'  
Rise Up To 11'